

# Infrastructure Upgrades

Saint Joseph Public Schools  
Saint Joseph, MI

Project Number: SJPS2304-0300

Saint Joseph Public Schools  
Infrastructure Upgrades  
Saint Joseph, MI

Title Sheet

ISSUE / DATE
2023-12-22 BIDS
_____
_____
_____
_____

DRAWN BY
CDB

PROJECT NO.
SJPS2304-0300

SHEET NO.
-----------

TG01



CABLING AND JACK LEGEND									
PURPOSE	PREMISE CABLING				JACKS				
	COLOR	RATING	MANUFACTURER	MODEL	TR COLOR	WA COLOR	MANUFACTURER	MODEL	SHIELDED
COPPER BACKBONE	BLUE	PLENUM	GENERAL CABLE	GENSPEED 6000	RED	RED	PANDUIT	CJ688TGRD	CJ688TGDRY
RESERVED					ORANGE	ORANGE		CJ688TGOR	
WIRELESS ACCESS POINTS					YELLOW	YELLOW		CJ688TGYL	CJ688TGYLY
FACILITIES					GREEN	GREEN		CJ688TGGR	CJ688TGGRY
SPECIAL NETWORK					BLUE	BLUE		CJ688TGBU	CJ688TGBUY
SURVEILLANCE CAMERAS					VIOLET	VIOLET		CJ688TGVL	CJ688TGVLV
RESERVED					BACK	BLACK		CJ688TGBL	CJ688TGY
POTS LINES					GRAY	GRAY		CJ688TGG	
GENERAL PURPOSE					WHITE	WHITE		CJ688TGW	CJ688TGWHY

FIBER LEGEND				
PURPOSE	TYPE	RATING	MANUFACTURER	MODEL
OUTSIDE PLANT	OUTSIDE PLANT	N/A	GENERAL CABLE	AQ***M1A-DT
BACKBONE	INDOOR/OUTDOOR	PLENUM	GENERAL CABLE	AP***1ANU-BK

PATCH CORD LEGEND		
PURPOSE	TR	WORK AREA
	COLOR	
GENERAL DATA	WHITE	
WIRELESS ACCESS POINTS	YELLOW	
FACILITIES	GREEN	
SURVEILLANCE CAMERAS	VIOLET	
PAGING	WHITE	
AV	WHITE	

RISER LEGEND	
SYMBOL	DESCRIPTION
	ZONE OR AREA
	BY OTHERS OR EXISTING
	NEW
	OPTIONAL
	PLUG INTO 120V RECEPTACLE
	CONNECT TO GROUND
	WIFI CONNECTION
	GENERIC RF CONNECTION
	BLUETOOTH CONNECTION
	CELLULAR CONNECTION
	8P8C (RJ45) NETWORK
	KEYED 8P8C (RJ45)
	SHIELDED 8P8C (RJ45)
	COMPONENT VIDEO
	COMPOSITE VIDEO
	SVIDEO
	HD15 (VGA) VIDEO
	DVI VIDEO
	HDMI VIDEO
	RED & WHITE RCA AUDIO
	3.5MM STEREO AUDIO
	1/4" STEREO AUDIO
	XLR MICROPHONE
	COAX TYPE "F"
	NEUTRIK NL4MP
	USB




ABBREVIATIONS	
ABBREVIATION	TERMINOLOGY
AC	ACCESS CONTROL
AFF	ABOVE FINISH FLOOR
ATS	AUTOMATIC TRANSFER SWITCH
AV OR AVV	AUDIO / VIDEO
BAS	BUILDING AUTOMATION SYSTEM
BB	BACKERBOARD
CIP	CAST IN PLACE
CLG	CEILING
CP	CONSOLIDATION POINT
EC	ELECTRICAL CONTRACTOR
EF	ENTRANCE FACILITY
EMT	ELECTRICAL METALLIC TUBING
EQ	EQUAL
EQUIV	EQUIVALENT
ER	EQUIPMENT ROOM
EXIST	EXISTING
GFCI	GROUND FAULT CIRCUIT INTERRUPTER
GRD	GROUND
HC	HORIZONTAL CROSS-CONNECT
IC	INTERMEDIATE CROSS-CONNECT
MC	MAIN CROSS-CONNECT
NIC	NOT IN CONTRACT
OC	ON CENTER
OSP	OUTSIDE PLANT
PBB	PRIMARY BONDING BUSBAR
PT	POKE-THROUGH
RBC	RACK BONDING CONDUCTOR
SBB	SECONDARY BONDING BUSBAR
SC	STRUCTURED CABLING
SCC	STRUCTURED CABLING CONTRACTOR
TBB	TELECOMMUNICATIONS BONDING BACKBONE
TE	TELECOMMUNICATIONS ENCLOSURE
TEBC	TELECOMMUNICATIONS EQUIPMENT BONDING CONDUCTOR
TO	TELECOMMUNICATIONS OUTLET
TR	TELECOMMUNICATIONS ROOM
TYP	TYPICAL
UNO	UNLESS NOTED OTHERWISE
UPS	UNINTERRUPTIBLE POWER SUPPLY
WA	WORK AREA

LIST OF DRAWINGS	
NUMBER	TITLE
TG01	Title Sheet
TG02	Technology General Information
T101	Brown ES Technology Plan - Composite
T102	E.P. Clarke ES Technology Plan - Composite
T103	Lincoln ES First Floor Technology Plan - Composite
T104A	Upton MS Technology Plan - Unit A
T104B	Upton MS Technology Plan - Unit B
T105	Saint Joseph HS Lower Floor Technology Plan
T106A	Saint Joseph HS Main Floor Technology Plan - Unit D
T106B	Saint Joseph HS Main Floor Technology Plan - Unit F & G
T301	Structured Cabling General Information
T302	Tech Rack Elevations
T303	Tech Rack Elevations
T304	Tech Rack Elevations
T305	Tech Rack Elevations
T306	Structured Cabling Details & Risers
T307	Structured Cabling Support Information
T308	Network Diagram


### GENERAL NOTES

- FOR DROPS INSTALLED ABOVE ACCESSIBLE CEILING, PROVIDE MAINTENANCE LOOP AS INDICATED ON TECHNOLOGY SYMBOL LEGEND. CABLE SHALL BE NEATLY COILED IN AN "S" LOOP AND SECURED TO BUILDING STRUCTURE AT DROP LOCATION FOR EASY RELOCATION.
- LOAD THE LATEST AVAILABLE STABLE FIRMWARE FOR ALL DEVICES WHEN THEY ARE SUPPLIED FOR THIS PROJECT.
- IN THE EVENT OF A DISCREPANCY BETWEEN TECHNOLOGY PLANS AND OTHER DISCIPLINES, CONTRACTOR SHALL SUBMIT AN RFI FOR CLARIFICATION.
- LABEL CABLES ACCORDING TO "CABLING LABEL DETAIL" ON THIS PAGE.

WORK SCOPE LEGEND					
CATEGORY	DEFINITION OF WORK	ELECTRICAL	STRUCT. CABLING	OWNER	NETWORK ELEC. CONTRACTOR
GENERAL DATA	DEMO EXISTING STRUCTURED CABLING EQUIPMENT (RETURN TO OWNER)		X		
	DEMO EXISTING STRUCTURED CABLING BACKBONE AND PREMISE CABLING		X		
	DEMO EXISTING ACCESS POINTS (RETURN TO OWNER)	X			
	PROVIDE ADAPTERS FOR RACEWAY, FLOORBOXES, ETC., TO ACCOMMODATE STANDARD FACEPLATES AND JACKS	X			
	PROVIDE STRUCTURED CABLING BACKBONE CABLING (AND TERMINATION)		X		
	PROVIDE STRUCTURED CABLING PREMISE CABLING (AND TERMINATION)		X		
	PROVIDE STRUCTURED CABLING PATCH CORDS		X		
	SUPPLY NETWORK ELECTRONICS				X
	CONFIGURE NETWORK ELECTRONICS				X
	INSTALL NETWORK ELECTRONICS				X
	CONNECT TECH EQUIPMENT TO GROUNDING BUSBARS		X		
	SUPPLY HARD-WIRED UPSes				X
	INSTALL HARD-WIRED UPSes				X
	CONNECT HARD-WIRED UPSes TO POWER				X
	PROVIDE IP ADDRESSES FOR NETWORK CONNECTED DEVICES				X
	CONFIGURE VLANs				X




NOTES:  
1. USED ON TECHNOLOGY FLOOR PLANS TO REFERENCE A DETAIL, ELEVATION, OR SYSTEM OF COMPONENTS ELEVATION ON ANOTHER SHEET.




NOTES:  
1. LOCATED NEXT TO A REVISION CLOUD FOR ANY REVISIONS AFTER BIDS HAVE BEEN RELEASED, BEFORE CONTRACT HAS BEEN AWARDED.




NOTES:  
1. LOCATED NEXT TO A REVISION CLOUD FOR ANY REVISIONS AFTER CONTRACT HAS BEEN AWARDED.




NOTES:  
1. RFI (REQUEST FOR INFORMATION) INDICATES A REVISION AND CORRESPONDING NOTE THAT DOES NOT AFFECT BUDGET THAT WAS NOT INITIATED BY TECHNOLOGY CONTRACTOR.  
2. TSI (TECHNOLOGY INFORMATION) TAG INDICATES A REVISION AND CORRESPONDING NOTE THAT DOES NOT AFFECT BUDGET.




NOTES:  
1. REFERENCE TO CORRESPONDING NOTES ON SAME SHEET THAT HAVE MORE INFORMATION RELATED TO SYMBOL.




NOTES:  
1. DRAWN AROUND REVISION AREA RELATED TO ANY ADDENDUM OR BULLETIN.




NOTES:  
1. HEAVY SOLID LINE REPRESENTS NEW TECHNOLOGY. COMPLETE INSTALLATION OFTEN REQUIRES ROUGH-IN, CABLING, FACEPLATE AND/OR DEVICE. SEE DRAWINGS FOR MORE DETAIL.



NOTES:  
1. THIN DASHED LINE REPRESENTS EXISTING TECHNOLOGY TO BE REMOVED. COULD REQUIRE DEMOLITION OF ROUGH-IN, CABLING, FACEPLATE AND/OR DEVICE. DEVICE MAY NEED TO BE SALVAGED FOR REINSTALLATION OR TURNED OVER TO OWNER. SEE DRAWINGS FOR MORE DETAIL.



NOTES:  
1. THIN SOLID LINE REPRESENTS EXISTING TECHNOLOGY TO REMAIN. NO WORK REQUIRED AT SPECIFIC LOCATION, BUT COULD REQUIRE EXISTING CABLING AND/OR DEVICES TO BE MAINTAINED DURING CONSTRUCTION TO SUPPORT SPECIFIC DEVICE. SEE DRAWINGS FOR MORE DETAIL.



### Cabling Label Detail

1. DEMO ALL ABANDONED CABLES BACK TO THEIR SOURCE.
2. DEMOED EQUIPMENT, WHOLE OR IN PART, SHALL BE PRESENTED TO OWNER FOR FIRST RIGHT OF REFUSAL BEFORE REMOVAL FROM SITE.
3. FLOOR PLANS ARE NOT PROVIDED FOR THE CENTRAL OFFICE, TRANSPORTATION BUILDING, PRESSBOX, AND STADIUM.



**AETECH  
DESIGN**


6100 NEWPORT ROAD SUITE #225, PORTAGE, MI 49002 268-203-2444 - AETECH DESIGN

## Brown ES Technology Plan - Composite

SHEET NO.

© 2023 AETD, ALL RIGHTS RESERVED.





DEMO GENERAL NOTES

1. DEMO ALL ABANDONED CABLES BACK TO THEIR SOURCE.
2. DEMOED EQUIPMENT, WHOLE OR IN PART, SHALL BE PRESENTED TO OWNER FOR FIRST RIGHT OF REFUSAL BEFORE REMOVAL FROM SITE.
3. FLOOR PLANS ARE NOT PROVIDED FOR THE CENTRAL OFFICE, TRANSPORTATION BUILDING, PRESSBOX, AND STADIUM.




ISSUE / DATE
2023-12-22 BIDS

DRAWN BY
CDB
PROJECT NO.
SJPS2304-0300

SHEET NO.
-----------

T102



DEMO GENERAL NOTES

1. DEMO ALL ABANDONED CABLES BACK TO THEIR SOURCE.
2. DEMOED EQUIPMENT, WHOLE OR IN PART, SHALL BE PRESENTED TO OWNER FOR FIRST RIGHT OF REFUSAL BEFORE REMOVAL FROM SITE.
3. FLOOR PLANS ARE NOT PROVIDED FOR THE CENTRAL OFFICE, TRANSPORTATION BUILDING, PRESSBOX, AND STADIUM.



Lincoln ES First Floor Technology Plan - Composite

3/32" = 1'-0"

Saint Joseph Public Schools  
Infrastructure Upgrades  
Saint Joseph, MI

Lincoln ES First Floor Technology Plan - Composite

ISSUE / DATE  
2023-12-22 BIDS

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

DRAWN BY

CDB

PROJECT NO.

SJPS2304-0300

SHEET NO.

T103



DEMO GENERAL NOTES	
1.	DEMO ALL ABANDONED CABLES BACK TO THEIR SOURCE.
2.	DEMOED EQUIPMENT, WHOLE OR IN PART, SHALL BE PRESENTED TO OWNER FOR FIRST RIGHT OF REFUSAL BEFORE REMOVAL FROM SITE.
3.	FLOOR PLANS ARE NOT PROVIDED FOR THE CENTRAL OFFICE, TRANSPORTATION BUILDING, PRESSBOX, AND STADIUM.

ISSUE / DATE
2023-12-22 BIDS

DRAWN BY
CDB
PROJECT NO.
SJPS2304-0300


SHEET NO.
-----------

T104A



DEMO GENERAL NOTES

- 1. DEMO ALL ABANDONED CABLES BACK TO THEIR SOURCE.
- 2. DEMOED EQUIPMENT, WHOLE OR IN PART, SHALL BE PRESENTED TO OWNER FOR FIRST RIGHT OF REFUSAL BEFORE REMOVAL FROM SITE.
- 3. FLOOR PLANS ARE NOT PROVIDED FOR THE CENTRAL OFFICE, TRANSPORTATION BUILDING, PRESSBOX, AND STADIUM.



Upton MS Technology Plan - Unit B

1/16" = 1'-0"


Saint Joseph Public Schools  
Infrastructure Upgrades  
Saint Joseph, MI

Upton MS Technology Plan - Unit B

ISSUE / DATE
2023-12-22 BIDS
-----
-----
-----
-----
-----
DRAWN BY
CDB
PROJECT NO.
SJPS2304-0300
SHEET NO.
T104B

DEMO GENERAL NOTES

- 1. DEMO ALL ABANDONED CABLES BACK TO THEIR SOURCE.
- 2. DEMOED EQUIPMENT, WHOLE OR IN PART, SHALL BE PRESENTED TO OWNER FOR FIRST RIGHT OF REFUSAL BEFORE REMOVAL FROM SITE.
- 3. FLOOR PLANS ARE NOT PROVIDED FOR THE CENTRAL OFFICE, TRANSPORTATION BUILDING, PRESSBOX, AND STADIUM.



6100 NEWPORT ROAD, SUITE #225, PORTAGE, MI 48002 269.303.2444 AETECH DESIGN

Saint Joseph Public Schools  
Infrastructure Upgrades  
Saint Joseph, MI

Saint Joseph HS Lower Floor Technology Plan

ISSUE / DATE  
2023-12-22 BIDS

-----  
-----  
-----  
-----


DRAWN BY  
CDB

PROJECT NO.  
SJPS2304-0300

SHEET NO.

T105

© 2023 AETD. ALL RIGHTS RESERVED.





Saint Joseph HS Lower Floor Technology Plan

1/16" = 1'-0"



DEMO GENERAL NOTES

1. DEMO ALL ABANDONED CABLES BACK TO THEIR SOURCE.
2. DEMOED EQUIPMENT, WHOLE OR IN PART, SHALL BE PRESENTED TO OWNER FOR FIRST RIGHT OF REFUSAL BEFORE REMOVAL FROM SITE.
3. FLOOR PLANS ARE NOT PROVIDED FOR THE CENTRAL OFFICE, TRANSPORTATION BUILDING, PRESSBOX, AND STADIUM.



Saint Joseph HS Main Floor Technology Plan - Unit D

1/16" = 1'-0"

Saint Joseph Public Schools  
Infrastructure Upgrades  
Saint Joseph, MI

Saint Joseph HS Main Floor Technology Plan - Unit D

ISSUE / DATE

2023-12-22 BIDS

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

DRAWN BY

CDB


PROJECT NO.

SJPS2304-0300

SHEET NO.


T106A

© 2023 AETD. ALL RIGHTS RESERVED.



DEMO GENERAL NOTES

1. DEMO ALL ABANDONED CABLES BACK TO THEIR SOURCE.
2. DEMOED EQUIPMENT, WHOLE OR IN PART, SHALL BE PRESENTED TO OWNER FOR FIRST RIGHT OF REFUSAL BEFORE REMOVAL FROM SITE.
3. FLOOR PLANS ARE NOT PROVIDED FOR THE CENTRAL OFFICE, TRANSPORTATION BUILDING, PRESSBOX, AND STADIUM.



Saint Joseph HS Main Floor Technology Plan - Unit F & G

1/16" = 1'-0"

Saint Joseph Public Schools  
Infrastructure Upgrades  
Saint Joseph, MI

Saint Joseph HS Main Floor Technology Plan - Unit F & G

ISSUE / DATE  
2023-12-22 BIDS

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----

-----


DRAWN BY  
CDB

PROJECT NO.  
SJPS2304-0300























SHEET NO.

T106B

© 2023 AETD. ALL RIGHTS RESERVED.















DATA LEGEND											
SYMBOL			DESCRIPTION	HEIGHT	DATA DROPS	NEW WORK		SURFACE MOUNT		NOTES	
EXISTING	DEMO					ROUGH-IN	FACEPLATE	ROUGH-IN	FACEPLATE	ELECTRICAL	LOW VOLTAGE
			DATA DROP - BLANK	18"AFF	0	1/T302	SEE NOTES	6/T302	SEE NOTES		1
			DATA DROP - (# INDICATED)	18"AFF	#	1/T302	SEE NOTES	6/T302	SEE NOTES		2
FB 	FB 		DATA DROP - FLOOR BOX	FLOOR	#	SEE ELEC. NOTES	SEE NOTES	N/A	SEE NOTES	7	2
CH 	CH 		DATA DROP - COUNTERHEIGHT	SEE ELEC. NOTES	#	1/T302	SEE NOTES	6/T302	SEE NOTES	8	2
FR 	FR 		DATA DROP - FURNITURE	18"AFF	#	5/T302	11/T302	5/T302	11/T302	9	6
CW 	CW 		DATA DROP - CASEWORK	18"AFF	#	3/T302	SEE NOTES	7/T302	SEE NOTES	10	2
			WIRELESS ACCESS POINT - CEILING MOUNT	CEILING	1	N/A	SEE NOTES	N/A	SEE NOTES		3, 13
			WIRELESS ACCESS POINT - WALL MOUNT	144"AFF	1	1/T302	8/T302	6/T302	8/T302		3
			ANALOG PHONE DROP	N/A	1	N/A	N/A	N/A	N/A	11	4
			WALL PHONE	54"AFF	1	1/T302	14/T302	6/T302	14/T302		5
			FACILITIES DROP	SEE ELEC. NOTES	#	N/A	SEE NOTES	N/A	SEE NOTES	12	13


DATA LEGEND NOTES	
1.	PROVIDE BLANK FACEPLATE.
2.	8/T302, 9/T302, OR 10/T302 DEPENDING ON THE NUMBER OF DROPS.
3.	PROVIDE 20 FEET OF MAINTENANCE LOOP FOR CABLE.
4.	TERMINATE ON 110 BLOCK IN TELECOMMUNICATIONS ROOM (TR).
5.	TERMINATE ON PATCH PANEL IN TECH CLOSET.
6.	ROUTE CABLES THROUGH FURNITURE TO FURNITURE FACEPLATE.
7.	3/T302 OR 4/T302 AS NEEDED.
8.	MATCH ELEC. ROUGH-IN HEIGHT, TYPICALLY 8" ABOVE COUNTERTOP.
9.	FACTORY CUT ROUGH-IN PROVIDED IN MODULAR FURNITURE.
10.	PROVIDE ROUGH-IN IN FIXED CASEWORK.
11.	COORDINATE LOCATION W/ EQUIPMENT SERVED.
12.	COORDINATE FINAL LOCATION W/ BUILDING AUTOMATION SYSTEM CONTRACTOR.
13.	USE 12/T302 OR 13/T302 DEPENDING ON THE NUMBER OF DROPS.

STRUCTURED CABLING NOTES	
1.	FOR ALL ALPHABETIC IDENTIFIERS THE LETTERS "O" AND "I" ARE NOT USED, TO PREVENT POSSIBLE CONFUSION WITH THE NUMBERS ZERO AND ONE.
2.	ALL ANALOG PHONE DROPS ARE TO BE TERMINATED IN TECH CLOSETS ON 110 PUNCH-DOWN BLOCKS MOUNTED ON BACKBOARD.

CABLING SUPPORT LEGEND			
SYMBOL	DESCRIPTION	NOTES	
		ELECTRICAL	LOW VOLTAGE
	1-1/2" EMT SLEEVE W/ BUSHINGS		
	1-1/2" EMT SLEEVE W/ BUSHINGS, SEAL ENDS W/ FIRE-PROOF PUTTY		
	1-1/2" EMT SLEEVE W/ BUSHINGS (UP)		
	1-1/2" EMT SLEEVE W/ BUSHINGS (DOWN)		
	4" EMT SLEEVE W/ BUSHINGS		
	S11 EZ-PATH SERIES 44 OR APPROVED EQUIVALENT		
	4" EMT SLEEVE W/ BUSHINGS (UP)		
	4" EMT SLEEVE W/ BUSHINGS (DOWN)		




Lacing Bar Detail  
NTS




Typical Numbering for 48-Port Patch Panel  
6"x1'-0"






Brown ES TC-A Tech Rack Elevation

- RACK EQUIPMENT SHALL BE:**
- DEMO
- (1) UPS - LIEBERT GXT3 WITH ADDITIONAL BATTERY PACK  
LEVITON PATCH PANELS
- EXISTING
- VERTICAL PDU  
PANDUIT PATCH PANELS
- NEW
- (1) RACK-MOUNT UPS W/ NETWORK MONITORING CARD - LIEBERT  
GXT5-3000LVRT2UXLN
- FIBER TERMINATIONS SHALL BE:**  
PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET  
RACK-MOUNT FIBER ENCLOSURE - PANDUIT FCE1U  
FIBER ADAPTER PANEL - PANDUIT FAP6WBUDLCZ
- ALL PATCH PANELS SHALL BE:**  
PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET  
48-PORT PATCH PANEL - PANDUIT CPPL48WBLY (PREMISE CABLING)  
24-PORT PATCH PANEL - PANDUIT CPPL24WBLY (BACKBONE)  
STRAIN RELIEF BAR - PANDUIT SRB19D5BL
- NETWORK ELECTRONICS SHALL BE:**
- DEMO
- (4) NETWORK SWITCH - CISCO CATALYST 2960-X  
(1) CISCO WIRELESS CONTROLLER  
(1) ROUTER - CISCO CATALYST 2901
- EXISTING
- (1) SITE SYNC TIME CONTROLLER
- NEW
- (4) NETWORK SWITCH - MERAKI MS250-48



Brown ES TC-B Tech Rack Elevation

- RACK EQUIPMENT SHALL BE:**
- DEMO
- (1) UPS -  
SURGE SUPPRESSORS - APC PNET1GB
- EXISTING
- PANDUIT PATCH PANELS
- NEW
- (1) RACK-MOUNT UPS W/ NETWORK MONITORING CARD - LIEBERT  
GXT5-3000LVRT2UXLN
- FIBER TERMINATIONS SHALL BE:**  
PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET  
RACK-MOUNT FIBER ENCLOSURE - PANDUIT FCE1U  
FIBER ADAPTER PANEL - PANDUIT FAP6WBUDLCZ
- ALL PATCH PANELS SHALL BE:**  
PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET  
48-PORT PATCH PANEL - PANDUIT CPPL48WBLY (PREMISE CABLING)  
24-PORT PATCH PANEL - PANDUIT CPPL24WBLY (BACKBONE)  
STRAIN RELIEF BAR - PANDUIT SRB19D5BL
- NETWORK ELECTRONICS SHALL BE:**
- DEMO
- (4) NETWORK SWITCH - CISCO CATALYST 2960-X
- EXISTING
- (1) SITE SYNC TIME CONTROLLER
- NEW
- (4) NETWORK SWITCH - MERAKI MS250-48




Brown ES TC-C Tech Rack Elevation

- RACK EQUIPMENT SHALL BE:**
- DEMO
- (1) UPS - LIEBERT GXT3 WITH ADDITIONAL BATTERY PACK  
FIBER PATCH PANEL
- EXISTING
- PANDUIT PATCH PANELS
- NEW
- (1) RACK-MOUNT UPS W/ NETWORK MONITORING CARD - LIEBERT  
GXT5-1500LVRT2UXLN  
(1) RACK-MOUNT PDU - MIDDLE ATLANTIC PD-915R-PL  
FIBER TERMINATION
- FIBER TERMINATIONS SHALL BE:**  
PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET  
RACK-MOUNT FIBER ENCLOSURE - PANDUIT FCE1U  
FIBER ADAPTER PANEL - PANDUIT FAP6WBUDLCZ
- ALL PATCH PANELS SHALL BE:**  
PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET  
48-PORT PATCH PANEL - PANDUIT CPPL48WBLY (PREMISE CABLING)  
24-PORT PATCH PANEL - PANDUIT CPPL24WBLY (BACKBONE)  
STRAIN RELIEF BAR - PANDUIT SRB19D5BL
- NETWORK ELECTRONICS SHALL BE:**
- DEMO
- (1) NETWORK SWITCH - CISCO CATALYST 2960-X
- NEW
- (1) NETWORK SWITCH - MERAKI MS250-48


- TECH CLOSET GENERAL NOTES**
1. TECHNOLOGY CLOSETS SHALL BE NON-SPRINKLER SPACES.
  2. GENERAL BUILDING HVAC SHALL NOT BE INSTALLED IN ANY TECHNOLOGY CLOSET. IF ACTIVE COOLING IS REQUIRED, DEDICATED LOCAL SYSTEMS SHOULD BE INSTALLED IN EACH TECH CLOSET.
  3. ALL OUTLETS IN THE TECHNOLOGY CLOSETS SHOULD BE ON UPS-BACKED, GENERATOR POWERED CIRCUITS.
  4. EQUIPMENT MOUNTED ON BACKERBOARD SHALL MAINTAIN PROPER CLEARANCES FOR OPERATION AND BE COORDINATED WITH OTHER DISCIPLINES PRIOR TO INSTALL. IF THERE IS A CONFLICT OF PLACEMENT.
  5. RACK SIZES SHOWN ARE TYPICAL AND MAY NOT MATCH EXISTING RACK SIZES. ACTUAL EQUIPMENT LAYOUT IN RACKS SHALL FOLLOW EQUIPMENT ORDER SHOWN IN ELEVATIONS, ALONG WITH PROPER LABELING AND CABLE MANAGEMENT. CONFIRM FINAL INSTALL LOCATION WITH OWNER.
  6. DEMOED EQUIPMENT, WHOLE OR IN PART, SHALL BE PRESENTED TO OWNER FOR FIRST RIGHT OF REFUSAL BEFORE REMOVAL FROM SITE.
  7. DEMO ALL ABANDONED EQUIPMENT AND CABLING, INCLUDING COAXIAL. DEMO CABLE TO SOURCE.
  8. DEMO ALL LEVITON PATCH PANELS AND REPLACE WITH PANDUIT PATCH PANELS.
  9. DEMO ALL POTS PATCH PANELS, CABLING, ASSOCIATED 110 BLOCKS, AND OTHER UNUSED POTS EQUIPMENT. DEMO CABLING TO SOURCE. PRIOR TO DEMO, CHECK FOR DIAL TONE ON ANY LINES. NOTIFY OWNER AND NET OF ANY DIAL TONE IF DISCOVERED.
  10. DEMO ALL UPS UNITS.
  11. REMOVE ALL BACKERBOARD-MOUNTED FIBER ENCLOSURES AND RE-INSTALL SPLICED CONNECTORS IN THEIR RESPECTIVE RACKS FIBER ENCLOSURE.
  12. SEE NETWORK DIAGRAM ON T306 FOR MORE DETAILS ON NETWORK ELECTRONICS AND THEIR LOCATIONS.
  13. RACK MOUNTED EQUIPMENT SHALL BE INSTALLED WITH ENOUGH CLEARANCE SO THAT THE RACK CAN FUNCTION PROPERLY. PATCH CORDS, POWER CORDS, AND RELATED CABLING SHALL NOT PREVENT DOORS FROM CLOSING, RACK FROM SWINGING, OR OTHER SIMILAR FUNCTIONS.
  14. EXISTING COPPER BACKBONE. PATCH CORDS, JACKS, AND PATCH PANELS TO REMAIN. RELOCATE PATCH PANELS TO THE TOP OF RACKS WHERE POSSIBLE.

- TECH CLOSET KEYED NOTES**
- 1 ENCLOSED SERVER RACK.
  - 2 UPS. INSTALL IN BOTTOM OF RACK.
  - 3 PDU.
  - 4 MOVE SITESYNC IQ TIME CONTROLLER INTO RACK AT OWNER'S DIRECTION.
  - 5 (2) EXISTING CONDUITS TO REMAIN




E.P. Clarke ES TC-A Tech Rack Elevation

- RACK EQUIPMENT SHALL BE:**
- DEMO
- (1) UPS  
LEVITON PATCH PANELS  
FIBER PATCH PANEL
- EXISTING
- VERTICAL PDU  
PANDUIT PATCH PANELS
- NEW
- (1) RACK-MOUNT UPS W/ NETWORK MONITORING CARD - LIEBERT  
GXT5-3000LVRT2UXLN  
(1) SURGE PROTECTION CHASSIS - APC PRM24  
(2) SURGE PROTECTION MODULE - APC PNETR6  
FIBER TERMINATION
- FIBER TERMINATIONS SHALL BE:**  
PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET  
RACK-MOUNT FIBER ENCLOSURE - PANDUIT FCE1U  
FIBER ADAPTER PANEL - PANDUIT FAP6WBUDLCZ  
RELOCATE FIBER ENCLOSURE TO RACK FROM BACKERBOARD
- ALL PATCH PANELS SHALL BE:**  
PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET  
48-PORT PATCH PANEL - PANDUIT CPPL48WBLY (PREMISE CABLING)  
24-PORT PATCH PANEL - PANDUIT CPPL24WBLY (BACKBONE)  
STRAIN RELIEF BAR - PANDUIT SRB19D5BL
- NETWORK ELECTRONICS SHALL BE:**
- DEMO
- (1) CISCO WIRELESS CONTROLLER  
(1) ROUTER - CISCO 2901
- EXISTING
- (1) SITESYNC IQ TIME CONTROLLER  
(4) NETWORK SWITCH - MERAKI MS250-48




E.P. Clarke ES TC-B Tech Rack Elevation

- RACK EQUIPMENT SHALL BE:**
- DEMO
- (1) UPS -  
SURGE PROTECTION CHASSIS - APC PRM24  
(1) SURGE PROTECTION MODULE - APC PNETR6
- EXISTING
- PANDUIT PATCH PANELS
- NEW
- (1) RACK-MOUNT UPS W/ NETWORK MONITORING CARD - LIEBERT  
GXT5-3000LVRT2UXLN  
(1) RACK-MOUNT PDU - MIDDLE ATLANTIC PD-915R-PL  
(1) SURGE PROTECTION CHASSIS - APC PRM24  
(4) SURGE PROTECTION MODULE - APC PNETR6
- FIBER TERMINATIONS SHALL BE:**  
PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET  
RACK-MOUNT FIBER ENCLOSURE - PANDUIT FCE1U  
FIBER ADAPTER PANEL - PANDUIT FAP6WBUDLCZ
- ALL PATCH PANELS SHALL BE:**  
PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET  
48-PORT PATCH PANEL - PANDUIT CPPL48WBLY (PREMISE CABLING)  
24-PORT PATCH PANEL - PANDUIT CPPL24WBLY (BACKBONE)  
STRAIN RELIEF BAR - PANDUIT SRB19D5BL
- NETWORK ELECTRONICS SHALL BE:**
- EXISTING
- (5) NETWORK SWITCH - MERAKI MS250-48  
(1) SITESYNC IQ TIME CONTROLLER




Lincoln ES TC-A Tech Rack Elevation

- RACK EQUIPMENT SHALL BE:**
- DEMO
- UPS - LIEBERT GXT3  
LEVITON PATCH PANELS
- EXISTING
- VERTICAL PDU  
PANDUIT PATCH PANELS
- NEW
- (1) RACK-MOUNT UPS W/ NETWORK MONITORING CARD - LIEBERT  
GXT5-3000LVRT2UXLN
- FIBER TERMINATIONS SHALL BE:**  
PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET  
RACK-MOUNT FIBER ENCLOSURE - PANDUIT FCE1U  
FIBER ADAPTER PANEL - PANDUIT FAP6WBUDLCZ
- ALL PATCH PANELS SHALL BE:**  
PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET  
48-PORT PATCH PANEL - PANDUIT CPPL48WBLY (PREMISE CABLING)  
24-PORT PATCH PANEL - PANDUIT CPPL24WBLY (BACKBONE)  
STRAIN RELIEF BAR - PANDUIT SRB19D5BL
- NETWORK ELECTRONICS SHALL BE:**
- DEMO
- (1) ROUTER - CISCO 2901
- EXISTING
- (1) SITE SYNC TIME CONTROLLER  
(3) NETWORK SWITCH - MERAKI MS250-48




Lincoln ES TC-B Tech Rack Elevation

- RACK EQUIPMENT SHALL BE:**
- DEMO
- UPS - LIEBERT GXT3 WITH ADDITIONAL BATTERY PACK
- EXISTING
- PANDUIT PATCH PANELS
- NEW
- (1) RACK-MOUNT UPS W/ NETWORK MONITORING CARD - LIEBERT  
GXT5-3000LVRT2UXLN
- FIBER TERMINATIONS SHALL BE:**  
PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET  
RACK-MOUNT FIBER ENCLOSURE - PANDUIT FCE1U  
FIBER ADAPTER PANEL - PANDUIT FAP6WBUDLCZ
- ALL PATCH PANELS SHALL BE:**  
PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET  
48-PORT PATCH PANEL - PANDUIT CPPL48WBLY (PREMISE CABLING)  
24-PORT PATCH PANEL - PANDUIT CPPL24WBLY (BACKBONE)  
STRAIN RELIEF BAR - PANDUIT SRB19D5BL
- NETWORK ELECTRONICS SHALL BE:**
- EXISTING
- (1) SITE SYNC TIME CONTROLLER  
(5) NETWORK SWITCH - MERAKI MS250-48



Upton MS TC-A Tech Rack 1 Elevation


- RACK EQUIPMENT SHALL BE:**
- DEMO
- LEVITON PATCH PANELS
- EXISTING
- VERTICAL PDU  
PANDUIT PATCH PANELS  
CONSOLIDATE ALL LAN FIBER CONNECTIONS IN THIS RACK. LEAVE WAN FIBER CONNECTIONS IN RACK 2
- NEW
- (1) RACK-MOUNT UPS W/ NETWORK MONITORING CARD - LIEBERT  
GXT5-3000LVRT2UXLN
- FIBER TERMINATIONS SHALL BE:**  
PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET  
RACK-MOUNT FIBER ENCLOSURE - PANDUIT FCE1U  
FIBER ADAPTER PANEL - PANDUIT FAP6WBUDLCZ
- ALL PATCH PANELS SHALL BE:**  
PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET  
48-PORT PATCH PANEL - PANDUIT CPPL48WBLY (PREMISE CABLING)  
24-PORT PATCH PANEL - PANDUIT CPPL24WBLY (BACKBONE)  
STRAIN RELIEF BAR - PANDUIT SRB19D5BL
- NETWORK ELECTRONICS SHALL BE:**
- DEMO
- (1) ROUTER - CISCO 2901
- EXISTING
- (5) NETWORK SWITCH - MERAKI MS250-48



Upton MS TC-A Tech Rack 2 Elevation


- RACK EQUIPMENT SHALL BE:**
- DEMO
- (2) UPS - LIEBERT GXT3 WITH ADDITIONAL BATTERY PACK  
LEVITON PATCH PANELS
- EXISTING
- VERTICAL PDU  
PANDUIT PATCH PANELS  
CONSOLIDATE ALL LAN FIBER CONNECTIONS IN RACK 1. LEAVE WAN FIBER CONNECTIONS IN THIS RACK
- FIBER TERMINATIONS SHALL BE:**  
PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET  
RACK-MOUNT FIBER ENCLOSURE - PANDUIT FCE1U  
FIBER ADAPTER PANEL - PANDUIT FAP6WBUDLCZ
- ALL PATCH PANELS SHALL BE:**  
PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET  
48-PORT PATCH PANEL - PANDUIT CPPL48WBLY (PREMISE CABLING)  
24-PORT PATCH PANEL - PANDUIT CPPL24WBLY (BACKBONE)  
STRAIN RELIEF BAR - PANDUIT SRB19D5BL
- NETWORK ELECTRONICS SHALL BE:**
- DEMO
- (1) ROUTER - CISCO 2901
- EXISTING
- (1) SYNOLOGY STORAGE DEVICE  
(1) SITE SYNC TIME CONTROLLER  
(1) SERVER - HP PROLIANT DL180 G6  
(1) SERVER - HP PROLIANT DL380 G7






Upton MS TC-B Tech Rack Elevation

- RACK EQUIPMENT SHALL BE:**
- DEMO
  - UPS - LIEBERT GXT3 WITH ADDITIONAL BATTERY PACK
  - EXISTING
  - VERTICAL PDU
  - PANDUIT PATCH PANELS
  - NEW
  - (1) RACK-MOUNT UPS W/ NETWORK MONITORING CARD - LIEBERT GXT5-3000LVRT2UXLN
- FIBER TERMINATIONS SHALL BE:**
- PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET
- RACK-MOUNT FIBER ENCLOSURE - PANDUIT FCE1U
- FIBER ADAPTER PANEL - PANDUIT FAP6WBUDLCZ
- ALL PATCH PANELS SHALL BE:**
- PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET
- 48-PORT PATCH PANEL - PANDUIT CPPL48WBLY (PREMISE CABLING)
- 24-PORT PATCH PANEL - PANDUIT CPPL24WBLY (BACKBONE)
- STRAIN RELIEF BAR - PANDUIT SRB19D5BL
- NETWORK ELECTRONICS SHALL BE:**
- EXISTING
  - (5) NETWORK SWITCH - MERAKI MS250-48



Upton MS TC-C Tech Rack Elevation

- RACK EQUIPMENT SHALL BE:**
- DEMO
  - UPS - LIEBERT GXT3 WITH ADDITIONAL BATTERY PACK
  - LEVITON PATCH PANELS
  - EXISTING
  - VERTICAL PDU
  - PANDUIT PATCH PANELS
  - NEW
  - (1) RACK-MOUNT UPS W/ NETWORK MONITORING CARD - LIEBERT GXT5-3000LVRT2UXLN
- FIBER TERMINATIONS SHALL BE:**
- PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET
- RACK-MOUNT FIBER ENCLOSURE - PANDUIT FCE1U
- FIBER ADAPTER PANEL - PANDUIT FAP6WBUDLCZ
- ALL PATCH PANELS SHALL BE:**
- PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET
- 48-PORT PATCH PANEL - PANDUIT CPPL48WBLY (PREMISE CABLING)
- 24-PORT PATCH PANEL - PANDUIT CPPL24WBLY (BACKBONE)
- STRAIN RELIEF BAR - PANDUIT SRB19D5BL
- NETWORK ELECTRONICS SHALL BE:**
- EXISTING
  - (4) NETWORK SWITCH - MERAKI MS250-48



Upton MS TC-D Tech Rack Elevation


- RACK EQUIPMENT SHALL BE:**
- DEMO
  - WALL-MOUNTED TECH RACK
  - UPS - LIEBERT GXT3 WITH ADDITIONAL BATTERY PACK
  - LEVITON PATCH PANELS
  - EXISTING
  - PANDUIT PATCH PANELS
  - UPON DEMO OF RACK, LEAVE ATTACHED CONDUITS TO REMAIN.
  - NEW
  - (1) WALL-MOUNTED TECH RACK - MIDDLE ATLANTIC DWR-24-32
  - (1) FRONT RACK DOOR - MIDDLE ATLANTIC FD-24
  - (1) RACK-MOUNT UPS W/ NETWORK MONITORING CARD - LIEBERT GXT5-3000LVRT2UXLN
  - (1) RACK-MOUNT PDU - MIDDLE ATLANTIC PD-915R-PL
- FIBER TERMINATIONS SHALL BE:**
- PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET
- RACK-MOUNT FIBER ENCLOSURE - PANDUIT FCE1U
- FIBER ADAPTER PANEL - PANDUIT FAP6WBUDLCZ
- ALL PATCH PANELS SHALL BE:**
- PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET
- 48-PORT PATCH PANEL - PANDUIT CPPL48WBLY (PREMISE CABLING)
- 24-PORT PATCH PANEL - PANDUIT CPPL24WBLY (BACKBONE)
- STRAIN RELIEF BAR - PANDUIT SRB19D5BL
- NETWORK ELECTRONICS SHALL BE:**
- EXISTING
  - (5) NETWORK SWITCH - MERAKI MS250-48

## TECH CLOSET GENERAL NOTES

1. TECHNOLOGY CLOSETS SHALL BE NON-SPRINKLER SPACES.
2. GENERAL BUILDING HVAC SHALL NOT BE INSTALLED IN ANY TECHNOLOGY CLOSET. IF ACTIVE COOLING IS REQUIRED, DEDICATED LOCAL SYSTEMS SHOULD BE INSTALLED IN EACH TECH CLOSET.
3. ALL OUTLETS IN THE TECHNOLOGY CLOSETS SHOULD BE ON UPS-BACKED, GENERATOR POWERED CIRCUITS.
4. EQUIPMENT MOUNTED ON BACKERBOARD SHALL MAINTAIN PROPER CLEARANCES FOR OPERATION AND BE COORDINATED WITH OTHER DISCIPLINES PRIOR TO INSTALL. IF THERE IS A CONFLICT OF PLACEMENT.
5. RACK SIZES SHOWN ARE TYPICAL AND MAY NOT MATCH EXISTING RACK SIZES. ACTUAL EQUIPMENT LAYOUT IN RACKS SHALL FOLLOW EQUIPMENT ORDER SHOWN IN ELEVATIONS, ALONG WITH PROPER LABELING AND CABLE MANAGEMENT. CONFIRM FINAL INSTALL LOCATION WITH OWNER.
6. DEMOED EQUIPMENT, WHOLE OR IN PART, SHALL BE PRESENTED TO OWNER FOR FIRST RIGHT OF REFUSAL BEFORE REMOVAL FROM SITE.
7. DEMO ALL ABANDONED EQUIPMENT AND CABLING, INCLUDING COAXIAL. DEMO CABLE TO SOURCE.
8. DEMO ALL LEVITON PATCH PANELS AND REPLACE WITH PANDUIT PATCH PANELS.
9. DEMO ALL POTS PATCH PANELS, CABLING, ASSOCIATED 110 BLOCKS, AND OTHER UNUSED POTS EQUIPMENT. DEMO CABLING TO SOURCE. PRIOR TO DEMO, CHECK FOR DIAL TONE ON ANY LINES. NOTIFY OWNER AND NETD OF ANY DIAL TONE IF DISCOVERED.
10. DEMO ALL UPS UNITS.
11. REMOVE ALL BACKERBOARD-MOUNTED FIBER ENCLOSURES AND RE-INSTALL SPLICED CONNECTORS IN THEIR RESPECTIVE RACKS FIBER ENCLOSURE.
12. SEE NETWORK DIAGRAM ON T303 FOR MORE DETAILS ON NETWORK ELECTRONICS AND THEIR LOCATIONS.
13. RACK MOUNTED EQUIPMENT SHALL BE INSTALLED WITH ENOUGH CLEARANCE SO THAT THE RACK CAN FUNCTION PROPERLY. PATCH CORDS, POWER CORDS, AND RELATED CABLING SHALL NOT PREVENT DOORS FROM CLOSING, RACK FROM SWINGING, OR OTHER SIMILAR FUNCTIONS.
14. EXISTING COPPER BACKBONE. PATCH CORDS, JACKS, AND PATCH PANELS TO REMAIN. RELOCATE PATCH PANELS TO THE TOP OF RACKS WHERE POSSIBLE.


## TECH CLOSET KEYED NOTES

- 1 ENCLOSED SERVER RACK.
- 2 UPS, INSTALL IN BOTTOM OF RACK.
- 3 PDU.
- 4 MOVE SITESYNC IO TIME CONTROLLER INTO RACK AT OWNER'S DIRECTION.
- 5 (2) EXISTING CONDUITS TO REMAIN




Upton MS TC-E Tech Rack Elevation

- RACK EQUIPMENT SHALL BE:**
- DEMO
  - UPS - LIEBERT GXT3 WITH ADDITIONAL BATTERY PACK
  - LEVITON PATCH PANELS
  - EXISTING
  - VERTICAL PDU
  - PANDUIT PATCH PANELS
  - NEW
  - (1) RACK-MOUNT UPS W/ NETWORK MONITORING CARD - LIEBERT GXT5-3000LVRT2UXLN
- FIBER TERMINATIONS SHALL BE:**
- PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET
- RACK-MOUNT FIBER ENCLOSURE - PANDUIT FCE1U
- FIBER ADAPTER PANEL - PANDUIT FAP6WBUDLCZ
- ALL PATCH PANELS SHALL BE:**
- PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET
- 48-PORT PATCH PANEL - PANDUIT CPPL48WBLY (PREMISE CABLING)
- 24-PORT PATCH PANEL - PANDUIT CPPL24WBLY (BACKBONE)
- STRAIN RELIEF BAR - PANDUIT SRB19D5BL
- NETWORK ELECTRONICS SHALL BE:**
- EXISTING
  - (4) NETWORK SWITCH - MERAKI MS250-48




SJHS TC-A Tech Rack 1 Elevation

- RACK EQUIPMENT SHALL BE:**
- EXISTING OWNER EQUIPMENT
  - NOT IN SCOPE. VERIFY WITH OWNER.




SJHS TC-A Tech Rack 2 Elevation

- RACK EQUIPMENT SHALL BE:**
- EXISTING OWNER EQUIPMENT
  - NOT IN SCOPE. VERIFY WITH OWNER.




SJHS TC-A Tech Rack 3 Elevation

- RACK EQUIPMENT SHALL BE:**
- EXISTING OWNER EQUIPMENT
  - NOT IN SCOPE. VERIFY WITH OWNER.



SJHS TC-A Tech Rack 4 Elevation




- RACK EQUIPMENT SHALL BE:**
- DEMO
  - (1) FLOOR STANDING UPS - LIEBERT INFINITY
  - EXISTING
  - (1) VERTICAL PDU
  - NEW
  - (1) FLOOR-STANDING UPS -
  - (1) RACK SHELF
- FIBER TERMINATIONS SHALL BE:**
- PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET
- RACK-MOUNT FIBER ENCLOSURE - PANDUIT FCE1U
- FIBER ADAPTER PANEL - PANDUIT FAP6WBUD\* CZ
- ALL PATCH PANELS SHALL BE:**
- PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET
- 48-PORT PATCH PANEL - PANDUIT CPPL48WBLY (PREMISE CABLING)
- 24-PORT PATCH PANEL - PANDUIT CPPL24WBLY (BACKBONE)
- STRAIN RELIEF BAR - PANDUIT SRB19D5BL
- NETWORK ELECTRONICS SHALL BE:**
- DEMO
  - (1) WIRELESS CONTROLLER - CISCO CATALYST 5500
  - (2) CORE SWITCHES - CISCO CATALYST 4500-X
  - (5) NETWORK SWITCH - CISCO CATALYST 2960-X
  - (1) ROUTER - CISCO CATALYST C2901
  - EXISTING
  - (1) FIREWALL
  - (1) IP PHONE BOX
  - NEW
  - (2) CORE SWITCH - CISCO CATALYST C9500-40X
  - (5) NETWORK SWITCH - MERAKI MS250-48



SJHS TC-A Tech Rack 5 Elevation







- RACK EQUIPMENT SHALL BE:**
- EXISTING
  - (1) VERTICAL PDU
- FIBER TERMINATIONS SHALL BE:**
- PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET
- RACK-MOUNT FIBER ENCLOSURE - PANDUIT FCE1U
- FIBER ADAPTER PANEL - PANDUIT FAP6WBUD\* CZ
- ALL PATCH PANELS SHALL BE:**
- PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET
- 48-PORT PATCH PANEL - PANDUIT CPPL48WBLY (PREMISE CABLING)
- 24-PORT PATCH PANEL - PANDUIT CPPL24WBLY (BACKBONE)
- STRAIN RELIEF BAR - PANDUIT SRB19D5BL
- NETWORK ELECTRONICS SHALL BE:**
- DEMO
  - (4) NETWORK SWITCH - CISCO CATALYST 2960-X
  - EXISTING
  - (1) BERRIEN RESA CPE - CISCO CATALYST 2960-S
  - (1) COMCAST CPE - CIENA 3916
  - NEW
  - (4) NETWORK SWITCH - MERAKI MS250-48






- ### TECH CLOSET GENERAL NOTES
1. TECHNOLOGY CLOSETS SHALL BE NON-SPRINKLER SPACES.
  2. GENERAL BUILDING HVAC SHALL NOT BE INSTALLED IN ANY TECHNOLOGY CLOSET. IF ACTIVE COOLING IS REQUIRED, DEDICATED LOCAL SYSTEMS SHOULD BE INSTALLED IN EACH TECH CLOSET.
  3. ALL OUTLETS IN THE TECHNOLOGY CLOSETS SHOULD BE ON UPS-BACKED, GENERATOR POWERED CIRCUITS.
  4. EQUIPMENT MOUNTED ON BACKERBOARD SHALL MAINTAIN PROPER CLEARANCES FOR OPERATION AND BE COORDINATED WITH OTHER DISCIPLINES PRIOR TO INSTALL. IF THERE IS A CONFLICT OF PLACEMENT.
  5. RACK SIZES SHOWN ARE TYPICAL AND MAY NOT MATCH EXISTING RACK SIZES. ACTUAL EQUIPMENT LAYOUT IN RACKS SHALL FOLLOW EQUIPMENT ORDER SHOWN IN ELEVATIONS, ALONG WITH PROPER LABELING AND CABLE MANAGEMENT. CONFIRM FINAL INSTALL LOCATION WITH OWNER.
  6. DEMOED EQUIPMENT, WHOLE OR IN PART, SHALL BE PRESENTED TO OWNER FOR FIRST RIGHT OF REFUSAL BEFORE REMOVAL FROM SITE.
  7. DEMO ALL ABANDONED EQUIPMENT AND CABLING, INCLUDING COAXIAL. DEMO CABLE TO SOURCE.
  8. DEMO ALL LEVITON PATCH PANELS AND REPLACE WITH PANDUIT PATCH PANELS.
  9. DEMO ALL POTS PATCH PANELS, CABLING, ASSOCIATED 110 BLOCKS, AND OTHER UNUSED POTS EQUIPMENT. DEMO CABLING TO SOURCE. PRIOR TO DEMO, CHECK FOR DIAL TONE ON ANY LINES. NOTIFY OWNER AND NETD OF ANY DIAL TONE IF DISCOVERED.
  10. DEMO ALL UPS UNITS.
  11. REMOVE ALL BACKERBOARD-MOUNTED FIBER ENCLOSURES AND RE-INSTALL SPLICED CONNECTORS IN THEIR RESPECTIVE RACKS FIBER ENCLOSURE.
  12. SEE NETWORK DIAGRAM ON T306 FOR MORE DETAILS ON NETWORK ELECTRONICS AND THEIR LOCATIONS.
  13. RACK-MOUNTED EQUIPMENT SHALL BE INSTALLED WITH ENOUGH CLEARANCE SO THAT THE RACK CAN FUNCTION PROPERLY. PATCH CORDS, POWER CORDS, AND RELATED CABLING SHALL NOT PREVENT DOORS FROM CLOSING, RACK FROM SWINGING, OR OTHER SIMILAR FUNCTIONS.
  14. EXISTING COPPER BACKBONE, PATCH CORDS, JACKS, AND PATCH PANELS TO REMAIN. RELOCATE PATCH PANELS TO THE TOP OF RACKS WHERE POSSIBLE.

- ### TECH CLOSET KEYED NOTES
1. ENCLOSED SERVER RACK.
  2. UPS, INSTALL IN BOTTOM OF RACK.
  3. PDU.
  4. MOVE SITESYNC IO TIME CONTROLLER INTO RACK AT OWNER'S DIRECTION.
  5. (2) EXISTING CONDUITS TO REMAIN








- RACK EQUIPMENT SHALL BE:**
- **EXISTING**
- FIBER CONNECTIONS  
PANDUIT PATCH PANELS
- FIBER TERMINATIONS SHALL BE:**  
*PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET*  
RACK-MOUNT FIBER ENCLOSURE - PANDUIT FCE1U  
FIBER ADAPTER PANEL - PANDUIT FAP6WBUD\*CZ
- ALL PATCH PANELS SHALL BE:**  
*PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET*  
48-PORT PATCH PANEL - PANDUIT CPPL48WBLY (PREMISE CABLING)  
24-PORT PATCH PANEL - PANDUIT CPPL24WBLY (BACKBONE)  
STRAIN RELIEF BAR - PANDUIT SRB19D5BL
- NETWORK ELECTRONICS SHALL BE:**
- **DEMO**
  - **NEW**
- (1) NETWORK SWITCH - CISCO CATALYST 2960-S  
(1) NETWORK SWITCH - MERAKI MS250-48

SJHS TC-J (Pressbox) Tech Rack Elevation


NTS



- RACK EQUIPMENT SHALL BE:**
- **NEW**
- PANDUIT PATCH PANELS  
(1) RACK-MOUNT UPS W/ NETWORK MONITORING CARD - LIEBERT GXT5-1000LVRT2UXLN
- FIBER TERMINATIONS SHALL BE:**  
*PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET*  
RACK-MOUNT FIBER ENCLOSURE - PANDUIT FCE1U  
FIBER ADAPTER PANEL - PANDUIT FAP6WBUD\*CZ
- ALL PATCH PANELS SHALL BE:**  
*PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET*  
48-PORT PATCH PANEL - PANDUIT CPPL48WBLY (PREMISE CABLING)  
24-PORT PATCH PANEL - PANDUIT CPPL24WBLY (BACKBONE)  
STRAIN RELIEF BAR - PANDUIT SRB19D5BL
- NETWORK ELECTRONICS SHALL BE:**
- **DEMO**
  - **NEW**
- (1) NETWORK SWITCH - CISCO CATALYST 2960-S  
(1) ROUTER - CISCO CATALYST 2901  
(1) NETWORK SWITCH - MERAKI MS250-24

Transportation TC-A Tech Rack Elevation

NTS




- RACK EQUIPMENT SHALL BE:**
- **DEMO**
  - **EXISTING**
  - **NEW**
- (1) RACK-MOUNT UPS - ALTRONIX  
PANDUIT PATCH PANELS  
(1) RACK-MOUNT PDU - APC  
PANDUIT PATCH PANELS  
(1) RACK SHELF  
(1) FIBER CONNECTION  
(1) RACK-MOUNT UPS W/ NETWORK MONITORING CARD - LIEBERT GXT5-2000LVRT2UXLN
- FIBER TERMINATIONS SHALL BE:**  
*PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET*  
RACK-MOUNT FIBER ENCLOSURE - PANDUIT FCE1U  
FIBER ADAPTER PANEL - PANDUIT FAP6WBUD\*CZ
- ALL PATCH PANELS SHALL BE:**  
*PROVIDE QUANTITY AS REQUIRED TO TERMINATE ALL CABLES IN CLOSET*  
48-PORT PATCH PANEL - PANDUIT CPPL48WBLY (PREMISE CABLING)  
24-PORT PATCH PANEL - PANDUIT CPPL24WBLY (BACKBONE)  
STRAIN RELIEF BAR - PANDUIT SRB19D5BL
- NETWORK ELECTRONICS SHALL BE:**
- **DEMO**
  - **NEW**
- (2) NETWORK SWITCH - CISCO CATALYST 9200L  
(1) ROUTER - CISCO CATALYST 2901  
(2) NETWORK SWITCH - MERAKI MS250-48

Central Office TC-A Tech Rack Elevation

NTS


- ### TECH CLOSET GENERAL NOTES
1. TECHNOLOGY CLOSETS SHALL BE NON-SPRINKLER SPACES.
  2. GENERAL BUILDING HVAC SHALL NOT BE INSTALLED IN ANY TECHNOLOGY CLOSET. IF ACTIVE COOLING IS REQUIRED, DEDICATED LOCAL SYSTEMS SHOULD BE INSTALLED IN EACH TECH CLOSET.
  3. ALL OUTLETS IN THE TECHNOLOGY CLOSETS SHOULD BE ON UPS-BACKED, GENERATOR POWERED CIRCUITS.
  4. EQUIPMENT MOUNTED ON BACKERBOARD SHALL MAINTAIN PROPER CLEARANCES FOR OPERATION AND BE COORDINATED WITH OTHER DISCIPLINES PRIOR TO INSTALL. IF THERE IS A CONFLICT OF PLACEMENT.
  5. RACK SIZES SHOWN ARE TYPICAL AND MAY NOT MATCH EXISTING RACK SIZES. ACTUAL EQUIPMENT LAYOUT IN RACKS SHALL FOLLOW EQUIPMENT ORDER SHOWN IN ELEVATIONS, ALONG WITH PROPER LABELING AND CABLE MANAGEMENT. CONFIRM FINAL INSTALL LOCATION WITH OWNER.
  6. DEMOED EQUIPMENT, WHOLE OR IN PART, SHALL BE PRESENTED TO OWNER FOR FIRST RIGHT OF REFUSAL BEFORE REMOVAL FROM SITE.
  7. DEMO ALL ABANDONED EQUIPMENT AND CABLING, INCLUDING COAXIAL. DEMO CABLE TO SOURCE.
  8. DEMO ALL LEVITON PATCH PANELS AND REPLACE WITH PANDUIT PATCH PANELS.
  9. DEMO ALL POTS PATCH PANELS, CABLING, ASSOCIATED 110 BLOCKS, AND OTHER UNUSED POTS EQUIPMENT. DEMO CABLING TO SOURCE. PRIOR TO DEMO, CHECK FOR DIAL TONE ON ANY LINES. NOTIFY OWNER AND NETD OF ANY DIAL TONE IF DISCOVERED.
  10. DEMO ALL UPS UNITS.
  11. REMOVE ALL BACKERBOARD MOUNTED FIBER ENCLOSURES AND RE-INSTALL SPLICED CONNECTORS IN THEIR RESPECTIVE RACKS FIBER ENCLOSURE.
  12. SEE NETWORK DIAGRAM ON T306 FOR MORE DETAILS ON NETWORK ELECTRONICS AND THEIR LOCATIONS.
  13. RACK MOUNTED EQUIPMENT SHALL BE INSTALLED WITH ENOUGH CLEARANCE SO THAT THE RACK CAN FUNCTION PROPERLY. PATCH CORDS, POWER CORDS, AND RELATED CABLING SHALL NOT PREVENT DOORS FROM CLOSING, RACK FROM SWINGING, OR OTHER SIMILAR FUNCTIONS.
  14. EXISTING COPPER BACKBONE, PATCH CORDS, JACKS, AND PATCH PANELS TO REMAIN. RELOCATE PATCH PANELS TO THE TOP OF RACKS WHERE POSSIBLE.

- ### TECH CLOSET KEYED NOTES
- 1 ENCLOSED SERVER RACK.
  - 2 UPS, INSTALL IN BOTTOM OF RACK.
  - 3 PDU.
  - 4 MOVE SITESYNC IO TIME CONTROLLER INTO RACK AT OWNER'S DIRECTION.
  - 5 (2) EXISTING CONDUITS TO REMAIN




SJHS Inner-Building Backbone Cabling Riser

NTS



Upton MS Inner-Building Backbone Cabling Riser

NTS



Brown ES Inner-Building Backbone Cabling Riser


NTS

CABLING DISTRIBUTION NOTES

1. PROVIDE 10 FEET OF MAINTENANCE LOOP AT TECHNOLOGY ROOM AND 1 FOOT OF MAINTENANCE LOOP AT WORK AREA FOR ALL CABLING UNLESS NOTED OTHERWISE.
2. FOR EACH RUN OF BACKBONE FIBER BETWEEN TECHNOLOGY ROOMS, TERMINATE 2 STRANDS. TEST ALL STRANDS.
3. SEE PATCH CORD LEGEND AND CABLING AND JACK LEGEND ON T002 FOR MORE INFORMATION REGARDING APPROPRIATE COLORS REQUIRED.
4. BACKBONE RISERS ARE ONLY SHOWN FOR BUILDINGS WHERE INNER-BUILDING BACKBONES ARE BEING REPLACED.
5. COPPER BACKBONE CABLING, PATCH CORDS, PATCH PANELS, AND JACKS TO REMAIN.


GROUNDING NOTES

1. ENSURE ALL GROUNDING CONNECTIONS TO RACKS AND CABLETRAYS ARE MAINTAINED.




Cable Support Coupling Detail (Cabletray)

NTS




Cable Support Assembly Detail (J-Hooks)

NTS




Cable Support Assembly Detail (Cabletray)

NTS




Cable Support Assembly Detail (Cabletray)

NTS




Cable Support Installation Detail (J-Hooks)

NTS



Cable Support Installation Detail (Cabletray)


NTS



Cable Support Installation Detail (Cabletray)


NTS






SJHS Network Diagram

NTS




HS Stadium Network Diagram

NTS




HS Pressbox Network Diagram

NTS




Central Office Network Diagram

NTS



Transportation Building Network Diagram

NTS



Brown ES Network Diagram

NTS

**Legend**

Remote Connection (Not on Page)

White: Intra-building Connection

Black: Inter-building Connection

Cloud External Services (Internet, Phone, etc.)

Router/Firewall

Switch or Generic Device

Wireless Access Point

Server

Building or Room

IP Phone

Grouped Interfaces LACP, EtherChannel, Multilink, etc.

# = Untagged VLAN ID

T = Tagged Interface

STP Failover/Redundant Link Typically Disabled

Media Speed		
Generic		100 Mb/s
<10 Mb/s		1 Gb/s
10 Mb/s		10 Gb/s

Media Type	
Generic	
Circuit	
UTP	

**GENERAL NETWORK NOTES**

- INCLUDE 7-YEAR NETWORK ADVANTAGE LICENSES FOR CORE SWITCHES AND 10-YEAR LICENSES FOR MERAKI EDGE SWITCHES.
- ALL CRITICAL EQUIPMENT SHALL BE CONNECTED TO BOTH CORE SWITCHES.
- FOR BUILDING-TO-BUILDING FIBER CONNECTIONS, USE LR SFPs UNLESS ER IS REQUIRED DUE TO BUILDING DISTANCE. FOR INTRA-BUILDING FIBER CONNECTIONS, USE LRM SFPs UNLESS CLOSET DISTANCES REQUIRE LR. USE OEM OPTICS FOR CISCO AND MERAKI FOR BASE BID.
- CONFIGURE ALL DUAL-UPLINK CONNECTIONS WITH LACP.
- BUILDING BACKBONE CONNECTION SHALL OPERATE AT 20 GB (2 X 10 GB) LINKS.
- INCLUDE DUAL POWER SUPPLIES FOR ALL SWITCHES.
- ALL BACKBONE SHALL BE CONFIGURED AS 802.11Q VLAN TRUNKS.
- ALL SWITCHES SHALL BE CONFIGURED TO SUPPORT VOICE VLAN.
- ALL SWITCHES SHALL BE CONFIGURED WITH QOS TO PRIORITIZE VOICE AND VIDEO TRAFFIC.
- RE-USE DISTRICTS EXISTING VLAN STRUCTURE.
- PROVIDE ALL SFP UNITS AND FIBER PATCH CORDS, STACKING CABLES, ETC. AS REQUIRED TO IMPLEMENT A FULLY FUNCTIONING, TURN-KEY NETWORK.
- CISCO AND MERAKI ARE USED AS THE BASIS OF DESIGN TO INTEGRATE WITH THE EXISTING NETWORK ENVIRONMENT. EQUIVALENT MANUFACTURERS MAY BE SUBMITTED AS A VOLUNTARY ALTERNATE.